

Upper Vallet Economic Cprporation

Proposal Schedule of Items

Proposal ID: 26578.00

Contractor: _____

Pay Item Number	Item Description	Approx. Quantity	Unit of Measure	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
100	Septic System Note 2 Below	1	Lump Sum				
200	Well Note 3 Below	1	Lump Sum				
300	Foundation	1	Lump Sum				
400	Masonry Walls	1	Lump Sum				
500	Exterior Wood Veneer/Roof/Windows/Doors	1	Lump Sum				
500	Interior Finish Work (Paint, tile, etc.)	1	Lump Sum				
700	Internal Plumbing and Fixtures	1	Lump Sum				
800	Electric Note 4 Below	1	Lump Sum				
800	HVAC	1	Lump Sum				
900	Site Remediation-loam and seed disturbed areas	1	Lump Sum				
1000	Performance Bond/Insurance	1	Lump Sum				
				TOTAL BID:			

Note 1	During Phase 1 all large rocks were removed from the building and septic field areas. During the construction of the septic system, no large rock were encountered and the material on site was adequate for fill over the system, thus eliminating the need to bring additional fill materials to the site.
Note 2	The Subsurface Wastewater System has been installed and inspected by the Local Plumbing Inspector. Remaining to be done under this contract is connecting the installed system to the building wastewater system in accordance with the permit (see "External Plumbing Permit" on Project Bid Proposals tab).
Note 3	The well has been drilled to a depth of 120' including casing to 51". Flow is 30+ GPM. Remaining to be done under this contract is connecting the water supply to the building including pitless adapter, pump, pressure tank including electric connections from the building to the well. 4" diameter conduit is in place and marked to
Note 4	Electric power has been installed on a pole adjacent to the building site and readily available during construction and for permanent connection to the building.