

Upper Vallet Economic Corporation

Proposal Schedule of Items

Proposal ID: 26578.00

Contractor: _____

Pay Item Number	Item Description	Approx. Quantity	Unit of Measure	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
100	Septic System including site remediation of septic field Note 1 Below	1	Lump Sum				
200	Well Note 2 Below	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
300	Foundation Note 3 Below	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
400	Masonry Walls Note 3 Below	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
500	Exterior Wood Veneer/Roof/Windows/Doors	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
600	Internal Plumbing and Fixtures	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
700	HVAC	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
800	Site Remediation-loam and seed disturbed areas	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
900	Performance Bond/Insurance	1	Lump Sum	LEAVE BLANK - NOT APPLICABLE FOR SUBSURFACE WASTEWATER DISPOSAL SYSTEM			
				TOTAL BID:			
Note 1	During Phase 1 previously all large rocks were removed from the location of the proposed septic field and tanks. Excavation should be greatly improved and much easier for the system installation						
Note 2	Water supply line from the building shall be installed to allow for gravity flow back to the well as part of winterization. There are Pitless Adapters with a small drilled hole which when used with an in-line "snifter valve" allows for backflow to the well.						
Note 3	Plans specify concrete block walls. Due to shortage of block masons the walls may be constructed using Insulated Concrete Forms or conventional Concrete Wall Forms. Bids must include engineering certification that the alternative method will meet the design and engineering specifications contained in the Plans.						